



NOTES

- A. CENTERLINE OF METER TO BE NO MORE THAN 36" FROM THE FLOOR.
- B. METER MUST BE MOUNTED HORIZONTALLY INSIDE OF BUILDING.
- C. USE STAINLESS STEEL OR BRASS NUTS AND BOLTS.
- D. METER BYPASS ASSEMBLY AND METER SETTING TO BE CONSTRUCTED OF COPPER.
- E. ALL PIPING TO BE THOROUGHLY SUPPORTED.
- F. THE CITY IS NOT RESPONSIBLE FOR MAINTENANCE OF INSIDE PLUMBING.
- G. PROVIDE APPROVED BACKFLOW PREVENTER REGISTERED WITH THE CITY.
- H. PROVIDE TWO OR THREE (18-22 GAUGE) CONDUCTOR WIRE TO OUTSIDE OF BUILDING NEAR ELECTRIC METER.
- I. BYPASS VALVE SHALL BE LOCKABLE.
- J. CURB STOP IS ONLY ITEM INSTALLED OUTSIDE.



CITY OF
SIDNEY

1"-3" COMPOUND METER WITH BYPASS

REVISIONS:	DATE APPROVED:
	06/03/2020
	PAGE No. 800-9