



**NOTES**

- A. CENTERLINE OF METER TO BE NO MORE THAN 36" FROM THE FLOOR.
- B. METER MUST BE MOUNTED HORIZONTALLY.
- C. FULL FACE FLANGE GASKETS AND STAINLESS STEEL OR BRASS NUTS AND BOLTS TO BE USED.
- D. METER BYPASS ASSEMBLY AND METER SETTING TO BE CONSTRUCTED OF D.I.P. CL53 OR PVC SCHEDULE 80.
- E. ALL PIPING TO BE THOROUGHLY SUPPORTED.
- F. THE CITY IS NOT RESPONSIBLE FOR MAINTENANCE OF INSIDE PLUMBING.

- G. PROVIDE APPROVED BACKFLOW PREVENTER REGISTERED WITH THE CITY.
- H. PROVIDE THREE (18-22 GAUGE) CONDUCTOR WIRE TO OUTSIDE OF BUILDING NEAR ELECTRIC METER.
- I. BYPASS VALVE SHALL BE LOCKABLE.